


Schedule-B

NAME OF THE WORK: Improvements Of Cement Concrete Roads & Rcc Drain At 2nd Cross Opp.St Marry's School 5th Cross KalyanaNagara 15th A Cross And 17th A&C Cross Adjusted To Dasarahalli Main Road And 4th Cross 6th Cross 3rd Main Road And Opp to CSI Holy Church Road In Ward No 13Shetty halli Sub-Division


Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per the direction of Engineer-in-charge of the work	Sqm	1767.15	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	222.03	5348.76	Rupees Five Thousand Three Hundred Forty Eight and Seventy Six Paise Only
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per the direction of Engineer-in-charge of the work	Cum	616.88	5874.52	Rupees Five Thousand Eight Hundred Seventy Four and Fifty Two Paise Only

Signature of the Contractor
EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010


 Executive Engineer
 Dasarahalli Division

4	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2016-17	Sqm	37.01	59413.00	Rupees Fifty Nine Thousand Four Hundred Thirteen Only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specification. complete as per the direction of Engineer-in-charge of the work	Sqm	5712	310.58	Rupees Three Hundred Ten and Fifty Eight Paise Only
6	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications.	Sqm	48.6	1873.00	Rupees One Thousand Eight Hundred Seventy Three Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work	Cum	1767.15	77.60	Rupees Seventy Seven and Sixty Paise Only


EXECUTIVE ENGINEER-1
 Signature of the Contractor
DIVISION
BENGALURU-560 010


 Executive Engineer,
 Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division